



L_204 DRIVE ENTRANCE II

KEY	LATIN NAME	COMMON NAME	SIZE	SIZE (OTHER)	NOTES	QUANTITY
TREES						
JV	Juniperus virginiana	Eastern Red Cedar	10'-12' Ht			3
PG	Picea glauca	White Spruce	14'-18' Ht		Or Pinus strobus	4
PA	Picea abies	Norway Spruce	18'-24' Ht			8
PS	Pinus strobus	Eastern White Pine	14'-18' Ht		Or Picea glauca	4
SHRUBS						
Cm	Cornus mas	Cornelian Cherry Dogwood	5'	7 gallon		1
Co	Corylopsis pauciflora	Buttercup Witchhazel	3'	7 gallon		1
Ca	Corylopsis spicata	Spike Winterhazel	3'	5 gallon		1
Fl	Fothergilla x intermedia 'Mount Airy'	Mount Airy Fothergilla	3'	3 gallon		2
HJ	Hamamelis x intermedia 'Jelena'	Jelena Witchhazel	5'	7 gallon		1
HD	Hamamelis x intermedia 'Diane'	Diane Witchhazel	5'	7 gallon		1
Vr	Viburnum rhytidophyllum	Leatherleaf Viburnum	4'	7 gallon		8
VINES						
Jn	Jasminum nudiflorum	Winter Jasmine		3 Gallon		6

- PROPERTY LINE
- EXISTING SURVEYED DECIDUOUS TREE
- EXISTING SURVEYED EVERGREEN TREE
- EXISTING TREES BASED OFF AERIAL PHOTO
- EXISTING SURVEYED WOODLAND EDGE
- PROPOSED TREES
- PROPOSED SHRUBS
- EXISTING CONTOURS
- PROPOSED HEDGE

- PLANTING NOTES**
1. CONTRACTOR IS RESPONSIBLE FOR DETERMINING THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCING WITH THE WORK.
 2. COORDINATE INSTALLATION OF PLANTS WITH INSTALLATION OF HARDSCAPE AND UTILITIES INCLUDING IRRIGATION AND LIGHTING.
 3. NO PLANT SUBSTITUTIONS TO BE MADE UNLESS AUTHORIZED IN WRITING BY DEA.
 4. ALL PLANTS TO BE PLACED IN THE FIELD BY LANDSCAPE ARCHITECT.
 5. OBTAIN SOIL TEST RESULTS FOR ALL SOIL TO BE USED IN TREE PITS PRIOR TO DELIVERY. FURNISH SOIL ANALYSIS BY A QUALIFIED SOIL-TESTING LABORATORY STATING PERCENTAGES OF ORGANIC MATTER, GRADATION OF SAND, SILT, AND CLAY; PH; AND MINERAL AND PLANT NUTRIENT CONTENT OF SOIL. SUBMIT TEST RESULTS TO LANDSCAPE ARCHITECT A MINIMUM OF 30 DAYS PRIOR TO PLANTING FOR ANALYSIS AND RECOMMENDATIONS FOR SOIL AMENDMENTS.
 6. SOIL TEST RESULTS WILL DETERMINE ACTUAL SOIL AMENDMENTS AND FERTILIZATION REQUIRED. ALL AMENDMENTS SHALL BE INCORPORATED INTO THE SOIL A MINIMUM OF 8 INCHES UNIFORMLY.
 7. FOR PLANTERS AND POTS WITH PERENNIALS AND ANNUALS USE METRO-MIX LIGHTWEIGHT SOIL OR SIMILAR APPROVED.
 8. 2" OF TRIPLE SHREDDED PINE BARK MULCH TO BE USED IN ALL PLANTING, EXCEPT GROUNDCOVER (1" DEPTH). CONTRACTOR TO DETERMINE MULCH QUANTITY.
 9. LARGE SHRUBS AND TREES TO BE ANCHORED WITH WIRES TO PREVENT UPROOTING IN HIGH WINDS.
 10. ALL SHRUB AND PERENNIAL PLANTING SHALL HAVE A REPLACEMENT GUARANTEE FOR A PERIOD OF ONE YEAR BEGINNING AT THE DATE OF CERTIFIED LANDSCAPE COMPLETION.
 11. ALL TREES SHALL HAVE A REPLACEMENT GUARANTEE FOR A PERIOD OF TWO YEARS BEGINNING AT THE DATE OF CERTIFIED LANDSCAPE COMPLETION.

MATCHLINE TO DWG L-205

MATCHLINE TO DWG L-203

A	Issued to Planning Dept	DE	09/03/20
REV	DESCRIPTION	APP.	DATE



176 Moog Road
Garrison
PLANTING PLAN
DRIVE ENTRANCE II

DATE	07/12/2020	STATUS	DRAFT
SCALE	1/8" = 1'-0"	DRAWN	DD
DWG. NO	L_204	APPROVED	DE

No dimensions are to be scaled from this drawing. All dimensions are to be checked on site. Area measurements for indicative purposes only. All drawings and design are the copyright property of David Eaton Associates. Reproduction of the drawings, specifications, related documents, and design, in whole or in part is strictly forbidden without written permission. © DAVID EATON ASSOCIATES
It is a violation of the law for any person, unless acting under the direction of a licensed landscape architect, to alter an item in any way. If an item bearing the seal of a landscape architect is altered, the altering landscape architect shall affix to his item the seal and the notation "altered by" followed by his signature and the date of such alteration, and a specific description of the alteration.